



The Screencore 4100 is a 31m heavy-duty stacker with the ability to build a stockpile of over 13m in height at massive production rates

Screencore 4100

- Cat 3.6 100kw Tier 4 (C4.4 LRC)
- 4m Tracks
- · 1200mm wide heavy belt
- Twin 640 drive on conveyor
- Check Valves on raise/lower
- · Impact rollers in feed area
- · Dump hopper with auger option
- · Full side skirting
- · Boomerang rear lift
- · Hydraulic head and tail fold
- Extended oil cooler



